BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT40263

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/25/2019-20, Date: 11-02-2020

Name of Work:Additional fund for R.K.Hegade nagara Samudaya Bhavan to extend compound and grills.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K R Santhosh Kumar ( )	
				In Figures	In Words
1	695.59	KSRRB 300-1. Earth work excavation by manual means in Ordinary Soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.all leads and lift etc., complete as directed by the Engineeri-in-charge	cum	144.68	Rupees One Hundred Forty Four and Sixty Eight Paise Only
2	850.5	Removing & Refixing stone slabs of drains and pointing in C.M (1:3) all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	sqm	116.85	Rupees One Hundred Sixteen and Eighty Five Paise Only
3	364.5	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc.- do - 7.5 cms thick complete.all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	sqm	779.03	Rupees Seven Hundred Seventy Nine and Three Paise Only
4	175.39	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 20kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications.all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Cum	5692.45	Rupees Five Thousand Six Hundred Ninety Two and Forty Five Paise Only
5	34.56	KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Cum	6102.0	Rupees Six Thousand One Hundred Two Only
6	1080	KSRB 5-14: Providing and constructing load bearing wall with solid concrete blocks having block density not less than 800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 confirming to IS 2185 (Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials labour charges, scaffolding, curing, hire charges of machineries etc., complete as per specifications . KBS No.5.4 - do - with solid concrete blocks of size 400x150x200mm all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	sqm	1028.31	Rupees One Thousand Twenty Eight and Thirty One Paise Only
7	77.22	KSRRB M 1200-15.2: Plain / Reinforced cement concrete M20 with OPC Cement @ 320kgs, with 20mm and down size graded granite metal coars aggreagates @0.69 cum and fine aggreagates @ 0.46 cum, with superplastiser@ 3lts confirming to IS9103 -1999 Reaffirmed -2008, in open foundation complete as per drawing and technical specifications case-II, with batching plant transist mixer and concrete MORTH specification all leads and lift etc., complete as directed by the Engineeri-in-	cum	5405.33	Rupees Five Thousand Four Hundred Five and Thirty Three Paise Only
8	43.2	KSRB,15.1.3: Providing FLush pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Sqm	156.92	Rupees One Hundred Fifty Six and Ninety Two Paise Only
9	2000	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C. 1:2:4 with top and bottom width 114 and 165 mmrespectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including form work, curing, including cost of all materials, labour, hire charges of achinery, loading, unloading, lead and lift, transportation etc., complete.all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Nos	454.06	Rupees Four Hundred Fifty Four and Six Paise Only
10	270	KSRB 15-17.5: Applying priming coat over new wood surface and / or wood based surface preparing the surface after thoroughly cleaning oil, grease, dirt, and foreign matter, sand papering and knotting ready mix paint including cost of materials, labour, complete as per specifications. all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Sqm	55.64	Rupees Fifty Five and Sixty Four Paise Only
11	270	KSRB 15-17.6: Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications. all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Sqm	107.95	Rupees One Hundred Seven and Ninety Five Paise Only

Signature of Contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K R Santhosh Kumar ( )	
				In Figures	In Words
12	883.8	Providing and fixing RCC precast cover slab of 100mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge.	Sqm	2453.62	Rupees Two Thousand Four Hundred Fifty Three and Sixty Two Paise Only
13	54	Providing and fixing RCC precast cover slab of 250mm thick made out of CC 1:2:4 and jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge.	Sqm	5688.36	Rupees Five Thousand Six Hundred Eighty Eight and Thirty Six Paise Only
14	75.69	Providing and fixing M.S. Grill over existing compound wall as per using 16mm x 16mm M.S. Square rod at 150mm c/c spacing and 6mm x 40mm M.S. flats at horizontal and 6mm x12mm M.S. flat for ornamental design and providing shop edge design at the vertex of every vertical rods, including welding, grinding wherever necessary. All the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc., complete. The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, etc., complete as per specification.. all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Sqm	5975.13	Rupees Five Thousand Nine Hundred Seventy Five and Thirteen Paise Only
15	151.38	KSRB 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications. all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Sqm	67.89	Rupees Sixty Seven and Eighty Nine Paise Only
16	28.8	Supplying and fixing M.S rectangular poles made out of 2 equal angles of 65x656 mm welded together and fixed in CC (1:2:4) with 2 NOS 16 mm dia, M.S hold fast rods each of length 25 cms, including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineer in charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete), all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	m	955.98	Rupees Nine Hundred Fifty Five and Ninety Eight Paise Only
17	120	Providing and fixing M.S. Block pipe of 38 mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the two vertical poles (M.S rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the engineer in charge of work etc, complete including two coats of approved quality paint over one coat of shop paint, all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	m	454.06	Rupees Four Hundred Fifty Four and Six Paise Only
18	72	Providing chain link fencing 50 mm size of 8 guage properly stretched between rectangular poles and fixed with suitable bolts & nuts, the free ends shall bed welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the engineer – in charge of work including two coats of approved quality paint over one coat of shop paint, all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Sqm	795.72	Rupees Seven Hundred Ninety Five and Seventy Two Paise Only
19	1400	KSRRB M100-2. Loading and Unloading of stone boulders by manual means complete as per specification MORTH-100/chapter-1 all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Cum	77.68	Rupees Seventy Seven and Sixty Eight Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92